OTHER WORK SUGGESTED	Cellar Under Central Hall (B06)	Cellar under Store Room (B09)	Cellar under Office and Study (B10A)	Family Parlor (108)	Family Dining Room (109)	North Stair Hall (110)	Center Hall (111)	White Parlor (112)	South Stair Hall (113)	Store Room (114)	Mrs. R. E. Lee's Morning Room (115)	Office and Study (117)	Stair Landing (200)	Upstairs Hall (201)	Lee Girls' Dressing Room (202)	Lee Girls' Chamber (203)	Mary and Markie's Chamber (204)	Small Chamber (205)	Lee Boys' Chamber (206)	Col. and Mrs. R. E. Lee's Chamber (207)	Stairways and Landing Rooms
Install security system				●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●
Clean mantels				●	●			●								●	●		●		
Install lighting based on lighting study				●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●
Remove unstable canvas on walls and ceiling				●	●			●	●	●	●	●			●						
Record exposed surfaces with measured drawings and photographs, identify and date physical fabric				●	●			●	●	●	●	●			●						
Install new canvas so that treatment is reversible				●	●			●	●	●	●	●			●						
Paint entire room, colors based on valid study; if on canvas, restore textural appearance of canvas				●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●
Install period or reproduction hardware on doors based on hardware study				●	●			●		●	●	●	●	●	●	●	●	●	●	●	●
Restore furnishings based on approved furnishings plan				●	●	●	●	●	●	●	●	●		●	●	●	●	●	●	●	
Remove obsolete standpipe and firehose accordion		●								●			●								●